

<b>Project Name:</b>	<b>Federal Express UST Upgrade</b>
<b>Project Location:</b>	<b>New Orleans, Louisiana</b>
<b>Project Completion Date:</b>	<b>January 1999</b>
<b>Project Duration:</b>	<b>1 Month</b>
<b>Project Value:</b>	<b>\$7,500</b>
<b>Client Name:</b>	<b>Advent Environmental</b>
<b>Client Contact:</b>	<b>Mr. Frank Czajkowski</b>
<b>Client Phone Number:</b>	<b>813-885-9876</b>
<b>Technology Utilized:</b>	<b>UST Upgrade</b>

### **Project Description**

SEMS, Inc. was contracted to perform the closure of 1-10,000 gallon Underground Storage Tank. The closure involved the following tasks:

- \$ Filing all necessary closure notification forms with the State of Louisiana Department of Environmental Quality.
- \$ Obtaining the necessary City and Parish work permits.
- \$ Emptying the tank of all pumpable product.
- \$ Perform Petroscope internal tank testing to assure tank is upgradable.
- \$ Removal of 2 foot square concrete access holes for anodes.
- \$ Installation of cathodic protection for the tank and piping using sacrificial anodes.
- \$ Replacement of concrete at anode locations.
- \$ Performed tank tightness testing of the tank and product lines.

Prepare and submit the upgrade report to the State of Louisiana Department of Environmental Quality.